



N/F
F.R.A. DEVELOPMENT CORP.
RECENTLY ACQUIRED BY
THE TOWN OF SEEKONK

EAST PROVIDENCE, RHODE ISLAND
SEEKONK, MASSACHUSETTS

LIMIT OF WORK
AT PROPERTY LINE

N/F
MONIZ

DETENTION BASIN

LEONARD
STREET

EXISTING PAPER COMPOSTING
WINDROW (TYP)

LIMIT OF WORK
AT PROPERTY LINE

100 yr. FLOOD
BASE FLOOD
Elevation
17

N/F
MULHERN



PLAN
SCALE: 1"=40'

CONSTRUCTION NOTES:

1. THE CONTRACTOR SHALL CALL DIGSAFE AT 1-800-322-4844 AT LEAST 72 HOURS, SATURDAYS, SUNDAYS, AND HOLIDAYS EXCLUDED, PRIOR TO EXCAVATING AT ANY LOCATION. A COPY OF THE DIGSAFE PROJECT REFERENCE NUMBER(S) SHALL BE GIVEN TO THE OWNER PRIOR TO EXCAVATION.
2. LOCATIONS OF EXISTING PIPES, CONDUITS, UTILITIES, FOUNDATIONS AND OTHER UNDERGROUND OBJECTS ARE NOT WARRANTED TO BE CORRECT AND THE CONTRACTOR SHALL HAVE NO CLAIM ON THAT ACCOUNT SHOULD THEY BE OTHER THAN SHOWN.
3. STONE WALLS, FENCES, CURBS, ETC. SHALL BE REMOVED AND REPLACED AS NECESSARY TO PERFORM THE WORK, UNLESS OTHERWISE INDICATED. ALL SUCH WORK SHALL BE INCIDENTAL TO CONSTRUCTION OF THE PROJECT.
5. ALL AREAS DISTURBED BY THE CONTRACTOR BEYOND PAYMENT LIMITS SHALL BE RESTORED AT NO ADDITIONAL COST TO THE OWNER.
6. THE CONTRACTOR SHALL MAINTAIN SIDE SLOPES AND DRAINAGE SWALES DURING CONSTRUCTION TO PREVENT PONDING AND EROSION.
7. THE CONTRACTOR SHALL NOT STORE ANY APPARATUS, MATERIALS, SUPPLIES, AND EQUIPMENT ON DRAINAGE STRUCTURES OR WITHIN 100 FEET OF WETLANDS.
8. THE CONTRACTOR SHALL GRADE PROPOSED SLOPES TO MEET EXISTING SLOPES WHERE SHOWN ON PLANS, IN ACCORDANCE WITH THE MINIMUM AND MAXIMUM SLOPES SPECIFIED.
9. THE CONTRACTOR SHALL INSTALL THE EROSION CONTROL DEVICES BEFORE BEGINNING OTHER WORK ON SITE.
10. THE CONTRACTOR SHALL CONSTRUCT DRAINAGE SWALES AND DETENTION PONDS BEFORE BEGINNING OTHER WORK ON SITE.
11. THE CONTRACTOR IS ALLOWED TO USE THE TOWN WATER REQUIRED FOR CONSTRUCTION PURPOSES WITHOUT CHARGE.
12. THE CONTRACTOR IS TO PROVIDE A SHELTER TRAILER FOR THE RESIDENT ENGINEER, AS DESCRIBED IN THE SPECIFICATIONS, SECTION 01021, TEMPORARY FACILITIES.
13. ELEVATIONS REFERENCED ARE NATIONAL GEODETIC VERTICAL DATUM (NGVD), FORMERLY U.S. COAST AND GEODETIC SURVEY DATUM OF 1929.
14. LIMIT OF REFUSE TAKEN FROM EXISTING PLANS REFERENCED ON SHEET C-1. ADDITIONAL TEST PITS TO LOCATE LIMIT OF REFUSE MAY BE ORDERED BY THE ENGINEER.
15. IF THE CONTRACTOR EXPOSES ANY REFUSE AS A RESULT OF THE CONSTRUCTION ACTIVITIES, THE EXPOSED REFUSE SHALL BE COVERED AT THE END OF EACH WORKING DAY WITH A MINIMUM OF 6 INCHES OF DAILY COVER MATERIAL.
16. ALL REFUSE EXCAVATED FROM THE SIDE SLOPES OF THE LANDFILL SHALL BE PLACED ON THE LANDFILL WITHIN THE LIMIT OF WORK TO MEET REQUIRED GRADES, AS REQUIRED BY THE ENGINEER.
17. THE CONTRACTOR AND CONSTRUCTION ACTIVITIES SHALL NOT INTERFERE WITH THE OPERATION OF THE EXISTING RECYCLING STATION AND COMPOSTING AREA.

No.	Date	Dr. By	Ck. By	App. By	Description
					A P P R O V E D
					11/16/94



69-327

C-2